

# PALZIV NORTH AMERICA ACOUSTICAL PERFORMANCE TEST REPORT

#### **SCOPE OF WORK**

ASTM E90 AND ASTM E492 TESTING ON LIFEPROOF PLUSH CARPET OVER 11MM (7/16") HQ LIVING CARPET CUSHION

## **SPECIMEN TYPE**

152 mm Concrete Slab with Suspended Ceiling

#### **REPORT NUMBER**

M5263.16-113-11-R0

#### **TEST DATE**

06/19/21

#### **ISSUE DATE**

11/17/22

#### **RECORD RETENTION END**

06/19/25

#### **PAGES**

15

## **DOCUMENT CONTROL**

ATI 00629 (03/21/18) RTTDS-R-AMER-Test-2844 © 2017 INTERTEK





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

#### **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

#### **REPORT ISSUED TO**

## **PALZIV NORTH AMERICA**

7966 NC 56 Highway Louisburg, North Carolina 27549

#### **SECTION 1**

#### **SCOPE**

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by Palziv North America to perform testing in accordance with ASTM E90 AND ASTM E492 on Lifeproof Plush Carpet over 11mm (7/16") HQ Living Carpet Cushion. Results obtained are tested values and were secured by using the designated test methods. Testing was conducted in the VT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

#### **SECTION 2**

#### **SUMMARY OF TEST RESULTS**

DATA FILE NO.	M5263.16
SERIES/MODEL:	Lifeproof Plush Carpet over 11mm (7/16") HQ Living Carpet Cushion
STC	59
IIC	92
HIIC	96

**COMPLETED BY:** Morgan S. J. Kennedy COMPLETED BY: Daniel B. Mohler Technician - Acoustical Project Lead - Acoustical TITLE: TITLE: **Testing** Testing **SIGNATURE: SIGNATURE: DATE:** 11/17/22 DATE: 11/17/22

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of ACCREDITED the tested material, product or service must first be approved in writing by Intertek. The observations and test Testing Labora results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

#### **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

#### **SECTION 3**

#### **TEST METHODS**

The specimen was evaluated in accordance with the following:

**ASTM E90-09 (2016)**, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

ASTM E413-16, Classification for Rating Sound Insulation

**ASTM E492-09(2016)e1**, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

**ASTM E989-21**, Classification for Determination of Impact Insulation Class (IIC)

**ASTM E2235-04 (2020)**, Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

**ASTM E3222-20**, Standard Classification for Determination of High-Frequency Impact Sound Ratings

#### **SECTION 4**

#### MATERIAL SOURCE/INSTALLATION

The full test specimen was assembled on the day of testing by B&C. All materials provided by the client were installed on an existing B&C assembly (152 mm Concrete Slab with Suspended Ceiling) utilizing B&C-supplied materials. The assembly was installed in a steel test frame which was installed into the opening between the source and receive rooms in the test chamber. The test frame was isolated from the structure with dense neoprene gasket.

The total weight of the floor/ceiling assembly was 4206.8 kg. B&C will store samples of the test specimen for four years. Photographs of the test specimen are included in the report. A drawing of the test specimen is included in the report.

B&C will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by B&C for the entire test record retention period.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule, also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 5**

# **EQUIPMENT**

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET #	CAL DATE	
Data Acquisition Unit	National Instruments	PXI-4462	Data Acquisition Card	63763-1	10/20	*
Data Acquisition Unit	National Instruments	PXI-4462	Data Acquisition Card	63763-4	10/20	*
Data Acquisition Unit	National Instruments	PXI-4462	Data Acquisition Card	65124	02/21	*
Microphone Calibrator	Norsonic	1251	Acoustical Calibrator	65105	09/20	
Receive Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	64340	11/20	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	65617	09/20	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	65968	01/21	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	INT01089	02/21	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	INT00652	02/21	
Receive Room Environmental	Commit	T7540	Temperature and Humidity	63810	10/20	
Indicator	Comet	T7510	Transmitter	63811	10/20	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	65969	04/21	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63742	03/21	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63747	09/20	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63745	09/20	
Source Room Microphone	PCB Electronics	378C20	Microphone and Preamplifier	63744	09/20	
Source Room Environmental Indicator	Comet	T7510	Temperature and Humidity Transmitter 63812		10/20	
Tapping Machine	Norsonic	Nor277	Tapping Machine	INT00936	01/21	

<sup>\*</sup> The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

VT RECEIVE ROOM VOLUME	155.77 m³
VT SOURCE ROOM VOLUME	190 m³

## **SECTION 6**

## **LIST OF OFFICIAL OBSERVERS**

NAME	COMPANY
Michael A. Unnone	Intertek B&C
Daniel B. Mohler	Intertek B&C



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

#### **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

#### **SECTION 7**

#### **TEST PROCEDURE**

The microphones were calibrated before conducting the tests. The air temperature and relative humidity conditions were monitored and recorded during all measurements. The average temperature and humidity of both the source and receive rooms are listed in Sections 10 and 11. The maximum and minimum temperatures and humidities of the receive room from the duration of the test are listed in Sections 12 and 13.

The airborne transmission loss test was conducted in accordance with the ASTM E90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Two sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.

The impact sound transmission test was conducted in accordance with the ASTM E492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E492, and five sound absorption measurements were conducted at each of five microphone positions.

Detailed test procedures, data for flanking limit tests, repeatability measurements, and reference specimen tests are available upon request.

## **SECTION 8**

#### **TEST CALCULATIONS**

The STC (Sound Transmission Class), IIC (Impact Insulation Class), and HIIC (High-Frequency Impact Insulation Class) ratings were calculated in accordance with ASTM E413, ASTM E989, and ASTM E3222, respectively.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 9**

## **TEST SPECIMEN DESCRIPTION**

MATERIAL	DIMENSIONS (mm)	THICKNESS (mm)	MANUFACTURER AND SERIES	QUANTITY	AVERAGE WEIGHT				
Cornet	3048 by 3657.6	16.0	Lifeproof Plush	10.98 m²	2.69 kg/m <sup>2</sup>				
Carpet	Note: Loose laid								
Foam Carpet	1282.8 by 3048	11.0	(7/16") HQ Living	10.98 m²	0.59 kg/m²				
Cushion	Note: Loose laid			•	•				
	3023 by 3632	152.4	5000 PSI	10.98 m²	366.18 kg/m²				
Concrete Slab	25.4 mm from bo	Note: Installed in a test frame flush to the source room. Mats of #5 reinforcing bars were placed 25.4 mm from both the top and bottom of the slab, with bars spaced on 305 mm centers in both directions. No noticeable shrinkage or cracking was visible on the specimen.							
	38.1 by 2870	43.0	Armstrong HD8906	10.9 lin m	0.45 kg/m				
Drywall Main Beam	Note: Twelve gauge hanger wires were attached to the bottom side of the concrete at twelve locations and then to the main beams. The hanger wire was twisted around itself a minimum of three times within 76 mm creating a 305 mm plenum. The measured steel thickness was 0.5 mm.								
_	38.3 by 1219	37.3	Armstrong XL8945P	27.2 lin m	0.45 kg/m				
Cross Tee	Note: Inserted into the main beams on 610 mm centers. The measured steel thickness was 0.5 mm.								
Fiberglass	609.6 by 2438	88.9	Johns Manville Unfaced R- 13	10.98 m²	1.32 kg/m²				
Insulation	Note: Loose laid	Note: Loose laid onto the ceiling grid system							
	3023 by 1219	15.9	National Gypsum Gold Bond® Fire-Shield® Type X	10.56 m²	11.23 kg/m²				
Gypsum Panel	Note: Fastened with 25.4 mm fine thread drywall screws on 305 mm centers. Seams and perimeter sealed with Pecora AC-20® Acoustical Sealant and covered with pressure-sensitive tape.								



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 10**

## **TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS**

TEST DATE	6/19/2021							
DATA FILE NO.	M5263.16				ACCREDITED			
CLIENT	Palziv North Am	alziv North America						
DESCRIPTION	Concrete Slab, 43 m Tee, 88.9 mm Johns	mm Lifeproof Plush Carpet, 11 mm (7/16") HQ Living Foam Carpet Cushion , 152.4 mm 5000 PSI ncrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong XL8945P Cross e, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold nd® Fire-Shield® Type X Gypsum Panel						
SPECIMEN AREA	10.98 m²	Receive Temp.	21°C	Source Temp.	22.2°C			
TECHNICIAN	MAU	Receive Humidity	69%	<b>Source Humidity</b>	69%			

FREQ	BACKGROUND	ABSORPTION	SOURCE	RECEIVE	SPECIMEN	95%	NUMBER
FREQ	SPL	ABSORPTION	SPL	SPL	TL	CONFIDENCE	OF
(Hz)	(dB)	m²	(dB)	(dB)	(dB)	LIMIT	DEFICIENCIES
80	30.8	16.5	97	63	33	3.4	-
100	25.2	8.7	94	58	38	2.1	-
125	26.8	10.8	95	55	41	2.4	2
160	22.5	11.1	93	55	40	1.4	6
200	18.7	11.7	94	48	47	1.1	2
250	19.4	11.4	99	47	52	1.1	0
315	16.3	11.6	101	49	53	1.2	2
400	13.5	10.0	102	49	54	0.6	4
500	13.1	9.1	99	44	57	0.6	2
630	12.6	8.9	101	44	58	0.6	2
800	13.5	9.0	100	42	59	0.6	2
1000	13.2	9.2	99	39	62	0.6	0
1250	9.4	9.1	100	38	63	0.7	0
1600	5.9	9.4	100	35	65	0.6	0
2000	5.1	10.1	99	33	67	0.7	0
2500	4.9	11.3	98	31	69	0.3	0
3150	4.6	12.3	99	29	70	0.7	0
4000	5.1	13.2	100	27	72	0.5	0
5000	5.8	14.6	100	25	74	0.4	-
6300	6.5	17.0	95	19	75	0.7	-
8000	7.1	21.8	95	15	77	1.2	-
10000	7.4	21.8	91	9	80	1.3	-
STC Ratir	1g 59	(Sound Transmi	ssion Class)		Sum o	f Deficiencies	22

Notes:

- 1) Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.
- 2) Specimen TL levels listed in red are potentially limited by the laboratory flanking limit.
- 3) Specimen TL levels listed in *blue* indicate the lower limit of the transmission loss.
- 4) Specimen TL levels listed in green indicate that there has been a filler wall correction applied



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**


Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 11**

## **TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS GRAPH**

DATA FILE NO. CLIENT DESCRIPTION	16 mm Lifeproof Plu Concrete Slab, 43 m Tee, 88.9 mm Johns	·					
SPECIMEN AREA	10.98 m²	Receive Temp.	21°C	Source Temp.	22.2°C		
TECHNICIAN	MAU	Receive Humidity	69%	Source Humidity	69%		





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 12**

## **TEST RESULTS - IMPACT SOUND TRANSMISSION**

TEST DATE	6/19/2021							
DATA FILE NO.	M5263.16				ACCREDITED			
CLIENT	Palziv North Am	alziv North America						
DESCRIPTION	Concrete Slab, 43 m Tee, 88.9 mm Johns	mm Lifeproof Plush Carpet, 11 mm (7/16") HQ Living Foam Carpet Cushion , 152.4 mm 5000 PSI ncrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong XL8945P Cross e, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold and Fire-Shield Type X Gypsum Panel						
SPECIMEN AREA	10.98 m²	Maximum Temp.	21.6°C	Minimum Temp.	20.4°C			
TECHNICIAN	MAU	Max. Humidity	73%	Min. Humidity	66%			

FREQ	BACKGROUND SPL	ABSORPTION	NORMALIZED IMPACT SPL	95% CONFIDENCE	NUMBER OF
(Hz)	(dB)	m²	(dB)	LIMIT	DEFICIENCIES
80	29.1	16.5	36	1.6	DEFICIENCIES
100	23.5	8.8	28	1.3	8
125	22.0	10.4	23	0.8	3
160	22.8	10.4	21	1.2	1
200	16.9	12.3	16	0.8	0
250	18.5	12.1	18	1.8	0
315	17.8	11.5	16	1.1	0
400	14.3	10.0	16	0.8	0
500	14.6	9.0	14	0.8	0
630	16.2	8.9	12	0.7	0
800	15.8	9.1	13	0.8	0
1000	16.9	9.2	13	2.0	0
1250	12.9	9.0	8	0.5	0
1600	8.4	9.2	4	0.4	0
2000	6.4	10.1	3	0.3	0
2500	5.4	11.5	3	0.3	0
3150	4.9	12.1	3	0.2	3
4000	5.4	13.1	4	0.2	-
5000	6.1	14.5	5	0.2	-
6300	11.5	17.1	7	0.2	-
8000	9.6	21.8	9	0.2	-
10000	7.8	21.8	9	0.2	-
IIC Rating	92	(Impact Insulati	on Class)	um of Deficiencies	15

**Notes:** Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**


Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 13**

## **TEST RESULTS - IMPACT SOUND TRANSMISSION GRAPH**

TEST DATE  DATA FILE NO.  CLIENT	6/19/2021 M5263.16 Palziv North Am	•						
DESCRIPTION	Concrete Slab, 43 m Tee, 88.9 mm Johns	mm Lifeproof Plush Carpet, 11 mm (7/16") HQ Living Foam Carpet Cushion , 152.4 mm 5000 PSI ncrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong XL8945P Cross e, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold and Fire-Shield Type X Gypsum Panel						
SPECIMEN AREA	10.98 m²	Maximum Temp.	21.6°C	Minimum Temp.	20.4°C			
TECHNICIAN	MAU	Max. Humidity	73%	Min. Humidity	66%			





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 14**

# **TEST RESULTS - HIGH-FREQUENCY IMPACT SOUND TRANSMISSION**

TEST DATE	6/19/2021							
DATA FILE NO.	M5263.16				ACCREDITED			
CLIENT	Palziv North Am	Iziv North America						
DESCRIPTION	Concrete Slab, 43 m Tee, 88.9 mm Johns	mm Lifeproof Plush Carpet, 11 mm (7/16") HQ Living Foam Carpet Cushion , 152.4 mm 5000 PSI ncrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong XL8945P Cross e, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold and Fire-Shield Type X Gypsum Panel						
SPECIMEN AREA	10.98 m²	Maximum Temp.	21.6°C	Minimum Temp.	20.4°C			
TECHNICIAN	MAU	Max. Humidity	73%	Min. Humidity	66%			

FREQ	BACKGROUND SPL	ABSORPTION	NORMALIZED IMPACT SPL	95% CONFIDENCE	NUMBER OF
(Hz)	(dB)	m²	(dB)	LIMIT	DEFICIENCIES
400	14.3	10.0	16	0.8	1.2
500	14.6	9.0	14	0.8	0.0
630	16.2	8.9	12	0.7	0.0
800	15.8	9.1	13	0.8	0.6
1000	16.9	9.2	13	2.0	2.2
1250	12.9	9.0	8	0.5	0.1
1600	8.4	9.2	4	0.4	0.0
2000	6.4	10.1	3	0.3	1.4
2500	5.4	11.5	3	0.3	4.4
3150	4.9	12.1	3	0.2	7.3
HIIC Ratir	<mark>ng</mark> 96	(High-Frequency	/ Impact Insulation Class)	Sum of Deficiencies	17.3

**Notes:** Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**


Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 15**

## TEST RESULTS -HIGH-FREQUENCY IMPACT SOUND TRANSMISSION GRAPH

TEST DATE	6/19/2021						
DATA FILE NO.	TA FILE NO. M5263.16						
CLIENT	Palziv North Ar	Palziv North America					
DESCRIPTION	Concrete Slab, 43 r Tee, 88.9 mm John	16 mm Lifeproof Plush Carpet, 11 mm (7/16") HQ Living Foam Carpet Cushion, 152.4 mm 5000 PSI Concrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong XL8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel					
SPECIMEN AREA	10.98 m²	Maximum Temp.	21.6°C	Minimum Temp.	20.4°C		
TECHNICIAN	MAU	Max. Humidity	73%	Min. Humidity	66%		





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 16**

## **PHOTOGRAPHS**




Photo No. 1 Source Room View of Test Specimen Installation



Photo No. 2
Receive Room View of Test Specimen Installation



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 17**

## **DRAWING**



- 1-Floor Topping
- 2-Underlayment
- 3-Concrete Slab
- 4-Hanger Wire
- 5-Insulation
- 6-Ceiling Grid
- 7-Ceiling



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR PALZIV NORTH AMERICA**

Report No.: M5263.16-113-11-R0

Date: 11/17/22

## **SECTION 18**

## **REVISION LOG**

<b>REVISION</b> #	DATE	PAGES	DESCRIPTION
RO	11/17/22	N/A	Original Report Issue